

MONUMENT RECORD


Corner ID: **Wash_M15**

Quarter Corner

Sections 21 & 22- T10N-R01W, 2nd P.M.
Washington Township, Monroe County, Indiana

MONUMENT: Describe monument set or found (Include material type, scribing, distance above/below grade, dimensions.)
Found Boat Spike 0.2' below grade approximately 1' north of centerline of Fox Hollow Road.

MONUMENT LOCATION SKETCH:



WITNESS MONUMENT TIES

All ties to new Bearing Trees (BTs) are a mag nail set in a 1-1/2" plastic washer stamped "SURVEY MARKER - DO NOT REMOVE" and hack mark at the root crown (less than 12" above ground) perpendicular to the center of the tree, unless otherwise noted. BT diameters are noted as dbh and are measured approximately 4.5' above ground. Bearings are measured from the monument to the center of the BT, distances are measured from the monument to the mag nail.

ID	BEARING	DISTANCE	DESCRIPTION
Witness A	S 67d W	183.0'	Mag nail and washer set 0.5' above grade on the east side of a 13" Power Line Pole.
Witness B	S 14d E	17.5'	Found 35 M.P.H. sign post measured to center point 5' above grade as per 2004 monument record.
Witness C	S 44d W	70.1'	Found Fire Hydrant measured to a point on center peak north side as per 2004 monument record.
Witness D	N 59d W	56.0'	Mag nail and washer set 0.5' above grade on the east side of a 13" Power Line Pole.



OFFICE OF THE MONROE COUNTY SURVEYOR • Trohn Enright-Randolph

119 W 7th Street, Bloomington, IN 47404 • 812-349-2570 • surveyoroffice@co.monroe.in.us

Page 1 of 3

MONUMENT RECORD

Corner ID: **Wash_M15**

Quarter Corner

Sections 21 & 22- T10N-R01W, 2nd P.M.
Washington Township, Monroe County, Indiana

PHOTO IDENTIFIED: Photo Date: 06/29/2022



Photo Orientation & Description: Wash_M15 from above



Photo Orientation & Description: Looking west at Wash_M15

ORIGINAL OR SUBSEQUENT SURVEY EVIDENCE FOUND: Include, search area or areas, search procedure, etc.

Date of Field work/Search: 06/29/2022 By: JG & HJ Monument Found: Boat Spike BTs or Reference Objects Found: Found Witnesses B & C from 2004 monument record. New power line poles were placed in representation of Witness D Project #: Washington Monuments Field Book: 54/68 Equipment: The basis of bearings is Grid North System NAD83(2011)/Indiana West NAVD 88, Epoch 2010.0000, geoid12b_conus.db3, US Survey Feet, derived from GPS observations utilizing the Indiana Real-Time Network (INCORS). Coordinate data was collected with a Javad Triumph LS Network Rover. Coordinates are available upon request. Distances to witness ties were collected with a Leica Disto laser distance meter and a 100' measuring tape. Bearings to witness ties were collected with the internal magnetic compass of the Javad Triumph LS and were automatically adjusted to grid north and are approximately shown hereon for reference. Priority should be given to provided distances over bearings. Notes: All witness photos on file in the Monroe County Surveyors Office.

OTHER EVIDENCE: Describe corner location relative to nearby features and how to reach the corner location – note fences, roads, timber cutting lines, mow lines, clearings, plantings, streams, topo changes, etc.

Wash_M15 was found approximately 1' north of the centerline of Fox Hollow Road. Its excavation site can be spotted from the eastern entry for residential drive of 8480 N Fox Hollow Road. On the south side of the street sits the United Pentecostal Assembly Family Life Worship Center.

MONUMENT PRESERVATION: Describe work done to preserve existing monument.

Geodetic controls were captured for the monument. Two new witnesses were established.

THEORY OF LOCATION: Describe the theory of location for acceptance of this monument. Include monument origin and associated uncertainty.

The boat spike was previously witnessed by the Monroe County Surveyor, Steven V. Farkas, on December 27, 2004 using work conducted by Licensed Surveyor, Ben E. Bledsoe (LSS0559). Prior to that, the boat spike was set by Monroe County Surveyor, Michael Friley, on October 8, 1993 in order to replace a nail in bottle cap. At the time Bledsoe Tapp Co. verified that the nail in bottle cap was the monument held for this corner. References of File: Ben E. Bledsoe survey referencing nail in bottle cap, Boundary Survey for Yocum (1992), on file at the Recorder's Office as 00304246. Tracy L. McGill Survey, Location Control Route Survey Plat Proposed I-69 Section 5, Segment 4 Connaught Road to Morgan County Line (2013), on file at the Recorder's Office as 2013015455.IN. Christopher L. Porter survey, Retracement Boundary for April Ayers (2019), on file at the Recorder's Office as 2021022117.IN. Historic research has not yet been performed to prove the validity of this monument.



OFFICE OF THE MONROE COUNTY SURVEYOR • Trohn Enright-Randolph

119 W 7th Street, Bloomington, IN 47404 • 812-349-2570 • surveyoroffice@co.monroe.in.us

Page 2 of 3

MONUMENT RECORD

Corner ID: **Wash_M15**

Quarter Corner

Sections 21 & 22- T10N-R01W, 2nd P.M.
Washington Township, Monroe County, Indiana

Section 21

T10N-R01W

Washington

Section 22

T10N-R01W

Washington

CERTIFICATION:



Date: 4/18/2023

Trohn Enright-Randolph
Monroe County Surveyor

Date: 4/18/2023

Accepted by the Monroe County
Surveyor Review Board



OFFICE OF THE MONROE COUNTY SURVEYOR • Trohn Enright-Randolph

119 W 7th Street, Bloomington, IN 47404 • 812-349-2570 • surveyoroffice@co.monroe.in.us


Page 3 of 3

MONUMENT RECORD

STATE OF INDIANA ~ COUNTY OF MONROE

Section 21, Township 10 North, Range 1 West,

Monument Description & Remarks: Boat Spike Flush




COMPLETED By Ben E. Bledsoe

I, Ben E. Bledsoe, Registered Land Surveyor, here by certify that this document was prepared under my direction in accordance with the provisions of Section 17-3-64-4 through 17-3-64-8 of the Indiana Code, being Acts of 1965, Chapter 319; this 27th day of December, 2004 A.D.

Ben E. Bledsoe

Indiana Registered Land Surveyor No. S0559



MONUMENT RECORD

Corner I.D. #


M-15

STATE OF INDIANA - COUNTY OF MONROE

Section Twenty-one, 21, Township 10 North, Range 1 West

Monument Description & Remarks: East 1/4 Corner of Section - Found nail in
bottle cap, verified by Bledsoe Tapp Co. to be corner. Replaced with
Boat Spike, 0.9' North of centerline of Fox Hollow Road.

Recovery Tie Drawing



● At Corner



Not To Scale

State of Indiana
County of Monroe

Space
Reserved For
Recording
Officer

I, Michael W. Friley, hereby certify
that this document was prepared under my direction in
accordance with the provisions of Section 17-3-64-4
through 17-3-64-8 of the Indiana Code, being Acts of 1965,
Chapter 319; and the above data is given under my hand and
seal this 8th day of October, 1993 A.D.

Indiana Registered Land Surveyor No. _____ or

Monroe County Surveyor's Office
United States Government Agency

Monroe County Surveyor
Title

Field Book:

93-01

Page:

14